



जीव विज्ञान प्रतिष्ठान

INSTITUTE OF LIFE SCIENCES

(An Autonomous Institute of the Department of Biotechnology, Govt. of India)

304

NO: VIII-82 -MF/2011-12/ 730/ ILS

Dated: 06.04. 2015

Notice Inviting Tender

Sealed quotations are invited from eligible, approved and experienced Civil Contractors for the works "Construction of approach road to DG room, backside door of animal house and washing platform." at the Institute of Life Sciences, Nalco square, and Bhubaneswar. The quotation papers are available in the website of the Institute at www.ils.res.in./www.tender.gov.in Interested Contractors may download the quotation papers, complete the same and send the same to the undersigned as so to reach the undersigned on or before 21 /04 / 2015 , up to 3.00 PM. The quotations will be opened on the same day at 3.30 P.M. in presence of the intending bidders or their authorized representatives. Quotations received after due date & time will not be entertained. Institute is not responsible for any postal delay. Incomplete or conditional quotation is liable for rejection. The authority reserves the right to reject any or all the quotations without assigning any reasons thereof.

Terms and conditions:

1. The work will be executed based on the specification as stated in the tender document.
2. The contactors who are interested to participate in the tender shall furnish Xerox copies of their Registration Nos. / Trade License No., Tin No. & pan card.
3. They must have successfully executed at least one similar work of single order value not less than Rs. 100000/- for work during the last 3 years. Documentary proof (copy of W.O) must be submitted.
4. The work should be started immediately after issue of work order and should be completed within one month from the date of issue of work order. Otherwise, penalty @ 1% of tender value will be charged to the Contractor per week of delay.
5. No extension of time will be allowed, if the above work is not completed within the stipulated time. ILS reserves the right to get it completed through any other source without sending any intimation to the contractor.
6. After completion of the work the Contractor shall clean the site and remove debris from the site to outside of ILS.
7. The Contractor shall abide by the laws of the land for payments to labourers etc.
8. The work shall be executed based on the design approved by ILS.
9. The payment shall be made as per the actual measurement of the work done confirming to specification and design.
10. Income Tax, Sales Tax, etc. shall be deducted from the payment to be made to the Contractor as per the existing law.
11. The court situated at Bhubaneswar shall have jurisdiction to decide any dispute or litigation, if arises in future beyond the above mentioned rules & regulations.

Copy to:

- 1) Notice board, ILS
- 2) Finance & Accounts Dept.
- 3) Mr. S .S.Mohanty, for publication in the website of www.ils.res.in./www.tender.gov.in


Administrative Officer

Nalco Square, Bhubaneswar - 751 023, India

EPABX: +91-674-2300137, 2301460, 2301476, 2301219

Fax : +91-674-2300728, Website : www.ils.res.in

नालको स्कोयार, भुवनेश्वर-७५१०२३, इंडिया

ईपीएबिक्स : +९१-६७४-२३००१३७, २३०१४६०, २३०१४७६, २३०१२१९

फैक्स : +९१-६७४-२३००७२८, वेबसाईट : www.ils.res.in

Name of the Work: Construction of approach road to DG room, backside door of Animal house and washing platform.

Sl.No	Description of Item	Unit	Quantity	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be leveled and neatly dressed. All kinds of soil	Cum	17.50		
2	Disposal of excavated earth lead up to 50 mtr to 5 km from inside campus.	Cum	17.50		
3	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	cum	11.00		
4	Providing and laying in position cement concert in specified grade excluding the cost of centering and shuttering – All work up to plinth level. 1:4:8 (1 : cement :4 coarse sand, 8 graded stone aggregate 40 mm nominal size)	CUM	12.00		
5	Half brick work with F.P.S bricks of class designations 75 in superstructure above plinth level up to floor V level. Cement mortar 1:3 (1 cement: 3 coarse sand)	SQM	19.00		
6	Brick work with common burnt clay F.P.S. (non -modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	0.650		
7	12mm thick cement plaster. 1:4 (1 cement: 6 fine sand)	SQM	19.00		

8	Providing and laying in position cement concert in specified grade excluding the cost of centering and shuttering – All work up to plinth level. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	CUM	6.50
9	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	Cum	0.650
10	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Cold twisted bars	Kg	35.00
11	Centering and shuttering including strutting, propping etc. and removal of form for: Suspended floors, roofs, landings, balconies and access platform.	Sqm	5.00
Total Amount			

- (1) All charges shall include the cost of Labour, material, taxes and other incidentals. Nothing Extra shall be paid beyond the agreement rate.
- (2) The work should be executed as per CPWD / IS Specification.
- (3) The work will be done according to the direction of Engineer in charge.