BRIC ILS INSTITUTE OF LIFE SCIENCES SEEKING INSIGHTS INTO LIFE
ब्रीक - जीव विज्ञान संस्थान
BRIC - INSTITUTE OF LIFE SCIENCES
(An Autonomous Institute of the Department of Biotechnology, Govt. of India)

सीमित निविदा

सी. पी. डब्ल्यू. डी., डी. ओ. पी., एम. ई. एस., रेलवे और ओडिशा के राज्य पीडब्ल्यू. डी. (आर. एंड बी.) जैसे लोक निर्माण संगठनों के उपयुक्त वर्ग की स्थापित सिविल एजेंसियों/ठेकेदारों से निदेशक, जीवन विज्ञान संस्थान, भुवनेश्वर के लिए और उनकी ओर से नीचे उल्लिखित कार्य के लिए सीमित निविदाएं आमंत्रित की गई हैं छात्रावास खाना पकाने के क्षेत्र आई. एल. एस. परिसर-I में शेड जी. आई. शीट, ईंट की दीवार को दीवार की टाइल से बदलना और 3 नंबर के निकास पंखे को लगाना ". ताकि अधोहस्ताक्षरित व्यक्ति के कार्यालय में सुबह 04/11/2026 से पहले 11.00 पर पहुँचा जा सके और उसी दिन 03.30 pm पर खोला जाएगा। एजेंसियों या उनके अधिकृत प्रतिनिधि से बोली खोलने की उक्त अनुसूची तिथि और समय पर उपस्थित रहने का अनुरोध किया जाता है।

नियम और शर्तें:

1. कार्य प्रभारी अभियंता के निर्देश के अनुसार किया जाएगा।
2. कार्य आदेश जारी होने के 3 दिन बाद काम शुरू किया जाना चाहिए और कार्य आदेश जारी होने की तारीख से 15 दिनों के भीतर पूरा किया जाना चाहिए। अन्यथा, विलंब के प्रति सप्ताह विक्रेता से निविदा मूल्य के 1 प्रतिशत की दर से जुर्माना लगाया जाएगा।
3. दो (02) समान कार्यों का अर्थ है "भवन और शेड कार्य की मरम्मत और नवीनीकरण" प्रत्येक का मूल्य निविदा के लिए रखी गई अनुमानित लागत के 60 प्रतिशत से कम नहीं है या एक (01) समान कार्यों का अर्थ है पिछले 05 (पांच) वर्षों में निविदा के लिए रखी गई अनुमानित लागत के 80 प्रतिशत से कम मूल्य के "भवन और शेड कार्य की मरम्मत और नवीनीकरण"
4. कार्य पूरा होने के बाद ठेकेदार स्थल की सफाई करेगा और स्थल से आई. एल. एस. परिसर के बाहर मलबा हटाएगा, इसकी लागत संस्थान द्वारा वहन नहीं की जाएगी
5. निविदा में भाग लेने के इच्छुक विक्रेताओं को अपने पंजीकरण संख्या/व्यापार लाइसेंस संख्या, जी. एस. टी. संख्या और पैन कार्ड की ज़ेरॉक्स प्रतियां प्रस्तुत करनी होंगी।
6. उद्धृत दर में जी. एस. टी. सहित सभी आनुषंगिक शुल्क और कर शामिल होने चाहिए। इसके कारण कुछ भी अतिरिक्त नहीं
7. कार्यकाल और शर्तों के अनुसार विनिर्देशन और डिजाइन, ड्राइंग आदि की पुष्टि करते हुए किए गए कार्य के वास्तविक माप के अनुसार कार्य के सफल समापन के बाद भुगतान किया जाएगा।
8. अतिरिक्त वस्तुओं (बी. ओ. क्यू. में प्रदान नहीं की गई) के मामले में, डी. एस. आर. के अनुसार विचार किया जाएगा।
9. विभाग इस काम के लिए किसी भी मजदूर की आपूर्ति नहीं करेगा।
10. अधोहस्ताक्षरित व्यक्ति बिना किसी कारण के दिए गए एक या सभी उद्धरणों को अस्वीकार कर देगा।
11. काम पूरा होने के तुरंत बाद बिल प्राप्त होने पर भुगतान किया जाएगा।
12. पहला और अंतिम भुगतान किया जाएगा। कोई मध्यवर्ती भुगतान नहीं किया जाएगा।
13. नियम के अनुसार बिल से सांविधिक कटौती की जाएगी।

एओ (प्रभारी), आईएलएस, भुवनेश्वर
निदेशक, आई. एल. एस. के लिए और उनकी ओर से

प्रति: वित्त और लेखा विभाग।
में प्रकाशित: आई. एल. एस. वेबसाइट और नोटिस बोर्ड

BRIC ILS INSTITUTE OF LIFE SCIENCES SEEKING INSIGHTS INTO LIFE
ब्रीक - जीव विज्ञान संस्थान
BRIC - INSTITUTE OF LIFE SCIENCES
(An Autonomous Institute of the Department of Biotechnology, Govt. of India)

LIMITED TENDER

Limited tender in Sealed bids for the work mentioned below hereby invited by the undersigned for and on behalf of the Director, Institute of Life Sciences, Bhubaneswar from the established civil agencies / contractors of appropriate class of Public Works Organizations like CPWD, DOP, MES, Railways and State PWD (R&B) of Odisha for work "**Repair and replace of shed GI sheet, brick wall with wall tile & fixing of 3 no's exhaust fan at hostel cooking area ILS campus-I**." so as to reach in the office of the undersigned on before 04/11/2026 at 11.00 AM and will be opened on the same day at 03.30 PM. The agencies or their authorized representative is requested to be present on the said schedule date and time of opening of the bid.

Term & Conditions:

1. The work shall be carried out as per direction of Engineer in charge.
2. The work should be started in 03 day after issue of work order and should be completed within fifteen days from the date of issue of work order. Otherwise, penalty @ 1% of tender value will be charged to the vendor per week of delay.
3. Two (02) similar works mean" repair & renovation of building & shed work " each of value not less than 60% of estimated cost put to tender or one (01) similar works means" repair & renovation of building & shed work" of value not less than 80%of estimated cost put to tender in last 05 (Five) Years
4. After completion of the work the Contractor shall clean the site and remove debris from the site to outside of ILS premises, cost towards it will not be borne by the Institute
5. The vendors interested to participate in the tender shall furnish Xerox copies of their Registration Nos. / Trade License No., GST No. & pan card.
6. Rate quoted should be inclusive of all incidental charges and taxes including GST. Nothing extra on account of this .
7. The payment shall be made after successful completion of the work as per the actual measurement of the work done confirming to specification and design, drawing etc. as per term & condition.
8. In case of extra items (not provided in BOQ), same will be considered as per DSR.
9. The department shall not supply any labours for the work.
10. The undersigned shall be reject one or all quotations assigning without any reason.
11. The payment will be made immediately on receipt of bill after completion of work.
12. First and final payment will made. No intermediate payment will be done.
13. Statutory deductions shall be made from the bill as per rule.

Digitally signed by
BIRAJA PRASAD SAMAL
Date: 28-10-2026
13:05:44

A.O (I/C), ILS, BHUBANESWAR
For and on behalf of Director, ILS

Copy to: Finance & Accounts Dept.
Published in: ILS Website & Notice Board

BRIC ILS INSTITUTE OF LIFE SCIENCES SEEKING INSIGHTS INTO LIFE
ब्रीक - जीव विज्ञान संस्थान
BRIC - INSTITUTE OF LIFE SCIENCES
(An Autonomous Institute of the Department of Biotechnology, Govt. of India)

Bill of Quantity

Name of the work: Repair and replace of shed GI sheet, brick wall with wall tile & fixing of 3 no's exhaust fan at hostel cooking area ILS campus-I

Sl.	Description of items	Unit	Quantity	Rate	Amount
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	Sqm	40.00		
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	Sqm	40.00		
3	1:2:4 (1 cement: 2 coarse sand (zone-III) derived from natural sources: 4 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	1.00		
4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	Kg	85.00		
5	Providing and fixing precoated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer in charge. The sheet shall be fixed using self-drilling /self-tapping screws of size (5.5x 55 mm) with EPDM seal, complete up to any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Sqm	80.00		
6	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	Sqm	50.00		
7	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	Sqm	60.00		
8	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand) DSR-23	Cum	4.00		
9	15 mm cement plaster of mix 1:6 (1 cement: 6 coarse sand) including scaffolding height up to floor five from plinth level. DSR-23	Sqm	40.00		
10	Providing and fixing Ist quality ceramic **glazed wall tiles** conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing	Sqm	38.00		

BRIC ILS INSTITUTE OF LIFE SCIENCES SEEKING INSIGHTS INTO LIFE
ब्रीक - जीव विज्ञान संस्थान
BRIC - INSTITUTE OF LIFE SCIENCES
(An Autonomous Institute of the Department of Biotechnology, Govt. of India)

	in white cement mixed with pigment of matching shade complete.				
11	Providing & fixing MS base high speed exhaust fan of 12" dia with outside MS flap to protect rain water and laying of 25 mm ms conduit pipe and MS flexible pipe from junction point to fan point with necessary wiring with 1.5 sq.mm FR/FRLS copper wires inside conduits etc. as per instruction.	Each	3		
	Total amount				

1. All charges shall include the cost of Labour, material, taxes, GST and other incidentals. Nothing extra shall be paid beyond the agreement rate.
2. The work should be executed as per CPWD / IS Specification.
3. The work will be done according to the direction of Engineer in charge